



SAINI HEAVY ELECTRICAL & ENGINEERING CO. PVT. LTD.



AC/DC Hi Pot Testing



Surge Comparison Testing



Capitance & Tan Delta Measurement Systems

Quality is the most important aspect of our business.

Personal attention is paid to each & every work involved.

We are equipped with the best testing equipments to perform test on all types of jobs.

Testing is carried out at different stages of rewinding

1. Motor Testing before dismantling i.e. static testing
2. Flux test on core after stripping for detection of Hot spots
3. Test during Coil Making
4. Test during & after mounting of coils
5. Testing after assembly
6. Load Testing of DC Machines by Back to back Method

TESTING FACILITIES

- a) AC / DC Hi Pot Test
- b) Surge Comparison Test
- c) Tan Delta Test
- d) P I Value Test
- e) And all other routine tests
- f) No Load Running Test.

CLEANING FACILITIES

- a) Steam Cleaning
- b) CO2 Cleaning



Back to back load testing of DC Machine



VACCUM PRESSURE IMPREGNATION PLANT

Load testing of vertical DC Machines